

2

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20236-00-00

Operator's Full Name Petroleum Management, Incorporated.

Complete Address 1515 Wichita Plaza Building, Wichita, Kansas.

Lease Name Kurtz Well No. 1

Location NW-NW-NW Sec. 34 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4116

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company.

Address 1720 Wichita Plaza Building, Wichita, Kansas. License No.

Operation Completed: Hour 12:30 PM Day 27 Month 6 Year 1969

The above well was plugged as follows:

225'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1165' and displaced 100 Sx. cement thru
DP from 1165' to 840'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED

STATE CORPORATION COMMISSION
JUL 1 1969
CONSERVATION DIVISION
Wichita, Kansas

Signed: W. S. Nichols
Well Plugging Supervisor

I hereby certify that the above well was plugged as herein stated.
INVOICED
DATE 7-1-69
INV. NO. 28-W

07-01-1969