

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED
APR 11 1972
CONSERVATION DIVISION
Wichita, Kansas
04-11-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20539-00-00

Operator's Full Name Petroleum, Incorporated,

Complete Address 300 West Douglas, Wichita, Kansas.

Lease Name Kurtz ^{KCC} B _{cup} Well No. 1

Location NW-SE-NW Sec. 34 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4095'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Garvey Drilling Company,

Address Box #1164, Great Bend, Kansas. License No.

Operation Completed: Hour 12:30 PM Day 9 Month 4 Year 1972

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 110 Cu. Ft. cement
thru DP from 1050' to 725'. Pulled DP to 210' and displaced 30 Cu. Ft. cement thru
DP from 210' to 135'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 4/13/72

INV. NO. 5532-10