

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 6 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
06-06-1972

15-065-20548-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Don E. Pratt,

Complete Address P. O. Box #370, Hays, Kansas.

Lease Name John Rohleder Well No. 1

Location NW NW SW  
140' FNL & 140' FWL of SW/4 Sec. 34 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3855'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.       

Operation Completed: Hour 4:30 PM Day 4 Month 6 Year 1972

The above well was plugged as follows:

196'--8 5/8" Surface casing, cement circulated with 185 Sx.  
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement  
thru DP from 1250' to 925'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*  
Well Plugging Supervisor

DATE 6-6-72  
INV. NO. 5806-12