

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065 - 20304-00-00

Operator's Full Name Geo. Reed and C & G Drilling Company.

Complete Address 1301 Union National Building, Wichita, Kansas.

Lease Name Elmer <sup>KCCZAP</sup> Geno Well No. 1

Location NW-NW-SW Sec. 35 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4060'

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X

Other well as hereafter indicated         

Plugging Contractor C & G Drilling Company.

Address 1107 Union National Building, Wichita, Kansas. License No.         

Operation Completed: Hour 6:30 PM Day 2 Month 2 Year 1970

The above well was plugged as follows:

2011--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru  
DP from 1225' to 900'. - Pulled DP to 215' and displaced 25 Sx. cement thru DP from  
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION  
02-06-1970  
FEB 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: H. S. Nichols  
Well Plugging Supervisor

DATE 2/6/70

NO. 1381-U