

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1971

CONSERVATION DIVISION
Wichita, Kansas

07-13-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20470-00-00

Operator's Full Name Murfin Drilling Company.

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Sproul Well No. 1

Location CW/2-W/2-SE/4 Sec. 35 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 3817'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 2:15 AM Day 11 Month 7 Year 1971

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/14/71

INV. NO. 3991-W

Signed: N. S. Nichols
Well Plugging Supervisor