

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

AUG 14 1967
08-14-1967
CONSERVATION DIVISION
Wichita, Kansas

15-065-03500-00-00

Operator's Full Name D. G. Hansen,

Complete Address: Logan, Kansas.

Lease Name George Gano Well No. 2

Location SE-SE-SE Sec. 36 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4040'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 496

Operation Completed: Hour 12:00M Day 9 Month 8 Year 1967

The Above well was plugged as follows:

207'--8 5/8" Surface pipe, cement circulated.
4039'--5 1/2" Production casing cemented with 150 Sx. Top perforations @ 3995'.
Dakota section from 1030' to 1240'.
Sanded well back to 3950' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing and squeezed well with 6 Sx. gel (1560' to 1260') then
100 Sx. cement (1260' to 950') then 16 Sx. gel (950' to 210') then 20 Sx.
cement (210' to 150') then 3 Sx. gel (150' to 30') and 5 Sx. cement (30' to
bottom of cellar.) Maximum pump-in pressure 400#. FSIP--150#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Dehals*
Well Plugging Supervisor

DATE 8/14/67

INV. NO. 6130W