

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20146-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1968
CONSERVATION DIVISION
Wichita, Kansas
06-04-1968

Operator's Full Name Farmer & Aylward,

Complete Address: 909 First National Building, Wichita, Kansas.

Lease Name Sproul Well No. 1

Location NE-NW-SW Sec. 36 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4005

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: John O. Farmer, Incorporated,

Address: 379 W. Wichita, Russell, Kansas. License No.

Operation Completed: Hour 5:30AM Day 29 Month 5 Year 1968

The Above well was plugged as follows:

167'--8 5/8" Surface pipe, cement circulated with 130 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1190' and displaced 100 Sx. cement thru
DP from 1190' to 865'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from
185' to 125'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. D. Nichols
Well Plugging Supervisor

INVOICED

DATE 6/4/68
INV. NO. 7871-W