

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company,
Complete Address 650 Fourth National Bank Building, Wichita, Kansas.
Lease Name John J. Richmeier Well No. A-1
Location NE-NE-NE Sec. 2 Twp. 9 Rge. (E) (W) 25
County Graham Total Depth 4275'
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Above
Address _____ License No. _____

Operation Completed: Hour 11:00 AM Day 15 Month 1 Year 1970

The above well was plugged as follows:

152'--8 5/8" Surface casing, cement circulated with 115 Sx.
4105'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to
4081'. Top perforations from 3878' to 3884'.
Sanded well back to--3800' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 5 sacks hulls and 11 sacks gel and followed with
100 Sx. cement from 1200' to 875' then 17 sacks gel from 875' to 195' and followed
with 25 Sx. cement from 195' to 120' then 2 sacks gel from 120' to 30' and finally
10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--250#. Final
shut-in pressure--175#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: *M. L. P. Dikala*
Well Plugging Supervisor

INVOICED

DATE 1/19/70
INV. NO. 1276-U

JAN 19 1970
CONSERVATION DIVISION
Wichita, Kansas
1-19-70