

15-065-01630-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company.

Complete Address: 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Richmeier Well No. A-3

Location CN/2-SE-NE Sec. 2 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4053'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Barnes & Sons Pipe Pulling Company.

Address: Box #313, Russell, Kansas. License No. 9

Operation Completed: Hour 2:45 PM Day 7 Month 7 Year 1969

The Above well was plugged as follows:

160'--8 5/8" Surface casing, cement circulated.

4045'--5 1/2" Production casing cemented on bottom with 100 Sx. Top perforations @ 3882'.

Sanded well back to 3850' and set 5 Sx. cement with dimp bailer. Pulled 5 1/2" casing
and squeezed well initially with 5 sacks hulls and 11 sacks gel and followed with 100
Sx. cement from 965 to 640' then 11 sacks gel from 640' to 200' and followed with 20
Sx. cement from 200' to 140' then 3 sacks gel from 140' to 30' and finally 10 Sx.
cement from 30' to bottom of cellar. Maximum pump-in pressure--250#. Final shut-in
pressure--125#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/16/69
98-u

RECEIVED
STATE CORPORATION COMMISSION
JUL 16 1969
CONSERVATION DIVISION
Wichita, Kansas

Signed: M. L. Nichols
Well Plugging Supervisor

7-16-69