

15-065-02015-00-00

Form CP-3
Rev. 6-26-62

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1963

CONSERVATION DIVISION
Wichita, Kansas

8-15-63

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name Knoll *E KCC* Well No. ~~E-1~~

Location NE-NW-NW Sec. 4 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4035

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 6:15AM Day 11 Month 8 Year 1963

The Above well was plugged as follows:

130' -- 8 5/8" Surface pipe, cement circulated.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx cement
thru DP. Heavy mud to 140', set plug with 1/4 sack hulls and displaced 20
Sx cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/15/63
INV. NO. 9581-W

Signed: *N. D. Nichols*
Well Plugging Supervisor