

15-065-20618-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1973

CONSERVATION DIVISION
Wichita, Kansas

7-19-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Palomino Petroleum,

Complete Address 304 Insurance Building, Wichita, Kansas.

Lease Name Knoll ^{KCC} F 24P Well No. -F-1

Location NW-SW-NW Sec. 4 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 4070'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 5:45 AM Day 17 Month 7 Year 1973

The above well was plugged as follows:

210' --8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 150 Cu. Ft. cement thru DP from 1325' to 1000'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 7/19/73
INV. NO. 7654-W