

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-00724-00-00

LEASE NAME Wolf #1

WELL NUMBER _____

SPOT LOCATION SW NE NW

SEC. 6 TWP. 10 RGE. 20w (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 12/13/84

Plugging Completed 12/13/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Dane G. Hansen Trust

ADDRESS Box 187, Logan, Ks. 67646

PHONE # (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3878'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8 | 164' | none |
| | | | | 5 1/2" | 3873' | none |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plug job only - No pipe recovery. Plugged well with 25 cement mixed with 1 hull, 20 gel with 1 hull, and 125 sacks 50/50 poz 8% gel mixed with 1 hull down 5 1/2".

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347, Chse, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION
01-07-1985
IAN 07 1985
My Commission expires:
CONSERVATION DIVISION
Wichita, Kansas



SUBSCRIBED AND SWORN TO before me this 31st day of December, 19 84

Irene Hoover
Notary Public

15-163-00724-00-00

CONTRACTOR'S WELL LOG

OPERATOR P. G. Hanson PARTNERS WOLFE & CO
 LOCATION NEW 13 SW, Sec. 6-10-22E
 POOL NAME _____ COUNTY Roos STATE Kansas
 COMMENCEMENT DATE January 23, 1954 COMPLETION DATE February 5, 1954

LOG OF WELL

Elevation: 2207 F.S.
 All measurements from the top of rotary casing.

| DEPTH | TO | DESCRIPTION | DEVIATION FROM VERTICAL | REMARKS |
|-------|------|-------------|-------------------------|----------------|
| 0 | 165 | Shale | | |
| 165 | 230 | Shale | | |
| 230 | 700 | Shale | | |
| 700 | 750 | Sand | | |
| 750 | 1265 | Sand-shale | | |
| 1265 | 1485 | Sand | | |
| 1485 | 1555 | Red bed | 0° - 1500' | |
| 1555 | 1775 | Red bed | | |
| 1775 | 2030 | Imbricate | | |
| 2030 | 2350 | Shale-shale | 0° - 2000' | |
| 2350 | 2550 | Shale-lime | | |
| 2550 | 2600 | Lime-shale | 0° - 2500' | |
| 2600 | 2660 | Lime-shale | | |
| 2660 | 3020 | Shale | 0° - 3000' | |
| 3020 | 3165 | Lime-shale | | |
| 3165 | 3225 | Lime-shale | | |
| 3225 | 3430 | Lime-shale | | |
| 3430 | 3515 | Lime-shale | 0° - 3500' | |
| 3515 | 3561 | Lime-shale | | |
| 3561 | 3615 | Lime-shale | | |
| 3615 | 3640 | Lime | | DSE 3602-3615' |
| 3640 | 3655 | Lime-shale | | DSE 3642-3655' |
| 3655 | 3705 | Lime | | |
| 3705 | 3775 | Lime-shale | | |
| 3775 | 3840 | Lime-shale | | |
| 3840 | 3873 | Lime-shale | | |
| 3870 | 3878 | Lime-shale | | DSE 3873-3870' |

CASING PLACED IN WELL AFTER COMPLETION

Run 164.15' (5 jgs) 8-5/8" Surface casing.
 Run 3807.55' (125 jgs) 5-1/2" CD casing.

STATE OF KANSAS, COUNTY OF ROOSEVELT) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

G-G DRILLING CO.

By Vicky Jacobs Office Manager

Subscribed and sworn to before me this 05th day of February, 1954.

My commission expires: June 17, 1957

Richard Donaldson Notary Public

REC'D 1954
 W. H. CROW