

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-00563-00-00
API NUMBER

LEASE NAME Holmes #2

WELL NUMBER

SPOT LOCATION NE SE NW

SEC. 6 TWP. 10 RGE. 20w(E) or (W)

COUNTY Rooks

Date Well Completed

Plugging Commenced 12/13/84

Plugging Completed 12/13/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Dane G. Hansen Trust

ADDRESS Box 187, Logan, Ks. 67646

PHONE # (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3845'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	163'	none
				5 1/2"	3844'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plug job only - No pipe recovery. Plugged well with 6 hulls, 20 gel, & 300 sacks 50/50 poz 8% gel down 5 1/2".

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso
(Address) Box 347, Chase, KS. 67524

RECEIVED

STATE CORPORATION COMMISSION

01-07-1985
JAN 07 1985



SUBSCRIBED AND SWORN TO before me this 31st day of December, 1984

Irene Hoover
Notary Public

My Commission expires:

CONSERVATION DIVISION
Wichita, Kansas

15-163-00563-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. Hansen FARM NAME Holmes No. 2
 LOCATION NE SE NW Sec. 6-10-W
 POOL NAME _____ COUNTY Reeks STATE Kansas
 COMMENCEMENT DATE August 29, 1953 COMPLETION DATE September 8, 1953

LOG OF WELL

Elevation: 2268' R.B.
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	165	Shale		
165	760	Shale		
760	855	Sand		
855	1220	Shale		
1220	1272	Shale-Sand		
1272	1475	Sand		
1475	1670	Red Bed	0° - 1500'	
1670	1773	Shale-Shells		
1773	1810	Anhydrite		
1810	2160	Shale-Shells	0° - 2000'	
2160	2410	Lime-Shale		
2410	2555	Lime-Shale	0° - 2500'	
2555	2685	Lime-Shale		
2685	2885	Lime-Shale		
2885	2995	Lime-Shale		
2995	3145	Lime-Shale	0° - 3000'	
3145	3263	Lime-Shale		
3263	3355	Lime-Shale		
3355	3435	Lime-Shale		
3435	3510	Lime-Shale	0° - 3500'	
3510	3554	Lime-Shale		
3554	3596	Lime-Shale		Taking DST
3596	3620	Lime		
3620	3636	Lime		DST 3620-3636'
3636	3680	Lime-Shale		
3680	3740	Lime		
3740	3795	Lime-Shale		
3795	3838	Lime-Shale		
3838	3845	Lime-Shale		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 163.25' (5 jts) 8-5/8" Surface Casing.
 Ran 3849.16' (123 jts) 5-1/2" OD Casing

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.

The undersigned certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Dick Jacobs
 Office Manager

Subscribed and sworn to before me this 10th day of September, 1953.

My commission expires: 6/17/57

Barbara Donaldson
 Notary Public

10-16-1984