

15-163-03093-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 6 Twp. 10S Rge. 20 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines SW NW NE

Lease Owner D. G. Hansen

Lease Name Hinkhouse Well No. 1

Office Address Logan, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 7 1956

Application for plugging filed July 7 1956

Application for plugging approved July 7 1956

Plugging commenced July 8 1956

Plugging completed July 8 1956

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3926 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	165'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 160'.
Set plug. Put in 1/2 sack Hulls and 15 sacks of cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack Hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.

Address 107 Rule Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Vicky Jacobs (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vicky Jacobs

107 Rule Bldg. (Address)

Subscribed and sworn to before me this 10th day of July, 1956



Notary Public. State Corporation Commission

PLUGGING
FILE SEC 6 T 10 R 20W
BOOK PAGE 79 LINE 14

07-11-1956
CONSERVATION DIVISION

15-163-03073-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN WELL NAME HINKHOUSE #1

LOCATION SW NW NE SECTION 6-10-20W RIG NO. 1

COUNTY ROOKS STATE KANSAS

COMMENCEMENT DATE JUNE 28, 1956 COMPLETION DATE JULY 7, 1956

LOG OF WELL

Elevation 2291' rotary bushing.
All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	165	Surface Soil		
165	1310	Sand-Shale		
1310	1500	Sand		
1500	1781	Red Bed		
1781	1820	Anhydrite		
1820	1930	Shale		
1930	2288	Shale-Sand		
2288	2485	Lime-Shale		
2485	2646	Lime-Shale	0° - 2500	
2646	2740	Lime-Shale		
2740	2825	Lime-Shale	0° - 2750	
2825	2920	Lime-Shale		
2920	3050	Lime-Shale	0° - 3000	
3050	3180	Lime-Shale		
3180	3315	Lime-Shale	0° - 3250	
3315	3390	Lime-Shale		
3390	3455	Lime-Shale		
3455	3535	Lime-Shale	0° - 3500	
3535	3587	Lime-Shale		
3587	3645	Lime-Shale		
3645	3700	Lime-Shale		
3700	3780	Lime-Shale	-° - 3750	
3780	3840	Lime-Shale		
3840	3926	Lime-Shale-Chert		

CASING LEFT IN HOLE AFTER COMPLETION
SET 165' of 8-5/8" OD Surface Casing.

COUNTY OF SEDGWICK, STATE OF KANSAS) SS.

The undersigned hereby certifies that to the best of her knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Vicky Jacobs
Vicky Jacobs

Subscribed and sworn to before me this 10th day of July, 1956.

My commission expires:

Donna Rose Porter
Notary Public

PLUGGING
FILE SEC 6 T 10 R 20W
BOOK PAGE 79 LINE 14