


15-163-03398-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 10 Twp. 10 Rge. 20 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE NW SW
Lease Owner B & R Drilling, Inc.
Lease Name Downey Well No. 6
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7/7/52 19
Application for plugging filed 7/6/52 19
Application for plugging approved 7/6/52 19
Plugging commenced 7/7/52 19
Plugging completed 7/7/52 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 384 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	189	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 180', set wooden plug, mixed and poured 15 sacks of cement through drill pipe. Filled hole with mud to 40', set wooden plug, 1 sack hulls and 10 sacks cement, tie top plug to surface pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS COUNTY OF RUSSELL ss.
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis, Jr.
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of July 1952
My commission expires 6-17-54

Clara L. Linn Notary Public.



24-2675-S 2-52-20M
PLUGGING
FILE SEC 20 T 10 R 20
BOOK PAGE 29 LINE 18

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1952
07-19-1952
CONSERVATION DIVISION
Wichita, Kansas

15-163-03398-00-00

B & R Drilling, Inc.
Dewney #6

SE NW SW 10-10-20
Rooks County, Kansas

Total Depth: 3841'
Comm. 6/25/52
Comp. 7/2/52

Casing
8 5/8" Set @ 189'

Cement
130 sacks Lone Star

Formation	Depth
Surface soil-sand-shale	40
Shells-sand-shale	188
Shale-shells	900
Sand-shale	950
Sand-shale-shells	1100
Sand-shale	1370
Shale-shells	1590
Sand-shale	1690
Anhydrite	1725
Shale-shells	1963
Shale-lime	2115
Shale	2510
Lime	2590
Shale-lime	3340
Lime	3841'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Lora City

Subscribed and sworn to before me this 17th day of July, 1952.

Clara [Signature]

Notary Public

My commission expires: 6-17-54.

PLUGGING
FILE SEC 10T10 R 200
ROCK PAGE 29 LINE 18

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1952
CONSERVATION DIVISION
Wichita, Kansas