

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-0204700-00

API NUMBER 7-20-51

LEASE NAME Sparks

WELL NUMBER 2

3630 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 10 TWP. 10 RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 7-20-51

Plugging Commenced 9-30-91

Plugging Completed 9-30-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Griggs Oil, Inc.

ADDRESS 107 N. Market, Suite 800 Wichita, KS 67202

PHONE# (316) 267-7779 OPERATORS LICENSE NO. 5058

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-23-91 (date)

by David P. Williams Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation K C Depth to Top 3520 Bottom 3780 T.D. 3777

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
		surface	141	8 5/8	141	0
		surface	3416	5 1/2	3416	0

OCT 10 1991  
10-10-1991  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Old Perf. 3733-37 Perf. 1730-1015 Pumped in 5 1/2" casing w/20 sks. cement with 1/4 lb. Flocele.  
Pumped in 380 sks. cement with 1/4 lb. Flocele and 500# Hulls mixed in cement. Max. 800 lb.  
Shut In 400 lb. Release pressure Perf. 141' circulated cement. 400 sks. 60-40 poz.  
10% gel. 1/4 lb. Flocele 500# Hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Griggs Oil, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


Wilber D. Berg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wilber D. Berg

(Address) 107 N. Market, Suite 800  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 9th day of October, 19 91

Virginia Lee Smith  
Notary Public



My Commission Expires: August 25, 1992