

15-163-02042-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 5/2/52
LEASE NAME Hinkhouse
WELL NUMBER #4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

330 Ft. from S Section Line
2310 Ft. from E Section Line
SEC. 10 TWP. 10 RGE. 20 (E) or (W)
COUNTY Rooks
Date Well Completed 5/2/52
Plugging Commenced 12/3/96
Plugging Completed 12/3/96

LEASE OPERATOR Vess Oil Corporation
ADDRESS 8100 E. 22nd Street North, Bldg. 300
Wichita, KS 67226
PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/2/96 (date)
by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Pre ACO-1 If not, Is well log attached? Filed with Application to Plug

Producing Formation Arbuckle Depth to Top 3785 Bottom 3795 T.D. 3795

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surf	152	8-5/8	152	None
		surf	3785	5-1/2	3785	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Fished tubing out to 1581'; Perfed holes at 1581'; Ran tubing. Circ. hole with 100 sx cement, 50 sx cement w/350# hulls. Pulled tbq. Pumped 150 sx w/ 100# hulls down csg. Pumped 50 sx cement w/50#hulls down 8-5/8 x 5-1/2 annululs

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 31-24, Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

W.R. Horigan (Employee of Operator of (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) W.R. Horigan

(Address) _____

SUBSCRIBED AND SWORN TO before me this 3rd day of January, 1997

My Commission Expires: _____

MICHELLE D. HENNING
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 1/18/97

Notary Public

RECEIVED
KANSAS CORP COM
01-07-1997

15-163-02042-00-00

RECORDED
INDEXED
MAY 12 1952

SCHLUMBERGER WELL SURVEYING CORPORATION
HOUSTON, TEXAS



LATEROLOG SURVEY

COUNTY: ROOKS	COMPANY: CHAMPLIN REFG.	Location of Well
FIELD: MARCOTTE	WELL: HINKHOUSE NO. 4	SEC. 10-10S-20W
LOCATION: MARCOTTE	FIELD: MARCOTTE	SW SW SE
WELL: HINKHOUSE NO. 4	LOCATION: SEC. 10-10S-20W	LL GRL ML
COMPANY: CHAMPLIN REFG.	SW SW SE	Elevation: D.F.: 2239
	COUNTY: ROOKS	K.B.: 2242
	STATE: KANSAS	or G.L.: 2235
	FILING No.	

RUN No.	LATEROLOG	MICROLOG
Date	3-24/25-52	
First Reading	3784	3785
Last Reading	157	3400
Feet Measured	3627	385
Csg. Schlum.	158	---
Csg. Driller	157	157
Depth Reached	3788	
Bottom Driller	3787	
Depth Datum	SEE REMARKS	
Mud Nat.	MAGCOGEL	
" Density	10.4	
" Viscosity	39.5	
" Resist.	19 @ 48°F	@ °F
" Res. BHT	1 @ 102°F	@ °F
" pH	6 @ °F	@ °F
" Wtr. Loss	14 CC 30 min.	CC 30 min.
Max. Temp. °F	102	
Bit Size	7 7/8	
Dpr. Rig Time	5 HRS.	
Truck No.	838	
Recorded By	K. GIBBONS	
By	MR. H. E. MORGAN	

REMARKS: LATEROLOG — AO 16" n 2.5
 GAMMA RAY — SENSITIVITY 10
 TIME CONSTANT 1 ONE DETECTOR.
 MEASUREMENTS TAKEN FROM KELLY BUSHING 7 FEET ABOVE GROUND LEVEL.

"MICROLOG"	0	50	20
	0	500	20
LATEROLOG	0	500	
GAMMA RAY	Perm.	Brkn.	Perm.
	Radioactivity Increases		

