

API NUMBER 15-163-02038-00-00

LEASE NAME Downey

WELL NUMBER #1

SPOT LOCATION SE SE SW

SEC. 10 TWP. 10S RGE. 20W (E) or (W) (W)

COUNTY Rooks

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-31-86

Plugging Completed 4-10-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Sierra Petroleum Company, Inc.

ADDRESS P.O. Box 247 Wichita, Kansas 67201

PHONE # (316) 262-5403 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3789'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	183'	none
				5-1/2"	3782'	815'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged off bottom with sand to 3500' and 5 sacks cement. Shot pipe @3000', 2800', 2600', 2300', 2000', 1700', 815' and pulled a total of 25 joints (815') of 5-1/2" casing. Plugged surface with 50 cement w/2 hulls, 15 gel w/2 hulls, 50 cement w/1 hull, 10 gel and 50 cement, 60/40 pos, 10% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION

APR 23 1986  
04-23-1986  
CONSERVATION DIVISION  
Wichita, Kansas


(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 21 day of April, 1986

James Hoover  
Notary Public

My Commission expires: \_\_\_\_\_



13-163-02038-00-00

FORM 575

# LANE WELLS COMPANY

*Gamma Ray / Neutron*

A DIVISION OF DRESSER INDUSTRIES, INC.

FILE NO.	COMPANY	SIERRA PETROLEUM COMPANY	
	WELL	DOWNING NO. 1	
	FIELD	MARCOTTIE	
	COUNTY	ROOKS	STATE KANSAS
	LOCATION:	SE - SE - SW	
	SEC	TWP	RGE
	10	10	20
	Permanent Datum	BRADEN HEAD	Elev. 2218½
	Log Measured from	7½ ABOVE B. H.	7½ Ft. Above Permanent Datum
	Drilling Measured from	KELLY BUSHING	
			Other Service
			Elevations
			KB 2226
			DF 2224
			GL

Date	9-9-60
Run No.	LST SUB
Type Log	GAMMA RAY & N/N
Depth-Driller	3789
Depth-Logger	3789
Bottom logged Interval	3788
Top logged Interval	3250
Type Fluid in Hole	OIL & WTR
Salinity Ppm Cl.	
Density lb./Gal.	
Level	2935
Max. Rec. Temp. Deg. F	
Opr. Rig Time	
Recorded By	BARLOW
Witnessed By	HALL

Run No.	Bit	Bore Hole Record		Size	Wgt.	Casing Record	
		From	To			From	To
1	13-1/1	SURFACE	183	8-5/8	21	SURFACE	183
1	7-7/8	183	3782	5-1/2	14	SURFACE	3782

RECEIVED  
 STATE COMMISSION  
 MAR 17 1965  
 CONSERVATION DIVISION  
 Wichita, Kansas