

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Vincent Oil Corporation
Address: 155 N Market, Suite 700, Wichita, KS 67202
Phone: (316) 262-3573 Operator License #: 5004
Type of Well: ENHR Docket #: E-27,323
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
L.K.C. Depth to Top: 3800 Bottom: 3852 T.D. _____
Marmaton Depth to Top: 4321 Bottom: 4328 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-151-20,851-00-01
Lease Name: Fruit
Well Number: 3
Spot Location (QQQQ): _____ - NW - NW - SW
2310 Feet from North / South Section Line
4950 Feet from East / West Section Line
Sec. 19 Twp. 27 S. R. 15 East West
County: Pratt
Date Well Completed: 3-7-81
Plugging Commenced: 10-29-07
Plugging Completed: 10-31-07

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	363	0
				5 1/2	4599	2440

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Shot tubing off at 3200', Sand at 3200', bailed 5 sacks cement, pulled slips, cut surface off 4' below ground, had 18" stretch, ripped casing at 2630', worked pipe, ripped casing at 2440', came free, pulled up to 990', pumped 15 gel, 50 sacks cement, pulled to 390', pumped 50 sacks, pulled to 40', circulated with 20 sacks to surface, tore down floor and rig, emptied pit, cleaned up location,

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67526

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Vincent Oil Corporation

NOV 08 2007

State of KANSAS County, SEDGWICK, ss.

CONSERVATION DIVISION
WICHITA, KS

Richard A. Hiebsch (Employee of Operator) (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature)

(Address) 155 N. Market, Suite 700, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 7th day of November, 2007

Yolanda Eubanks
Notary Public

My Commission Expires:



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202