

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Vincent Oil Corporation

Address: 155 N Market, Suite 700, Wichita, KS 67202

Phone: (316) 262-3573 Operator License #: 5004

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Emporia Depth to Top: 3506 Bottom: 3510 T.D. _____
Mississippian Depth to Top: 4862 Bottom: 4872 T.D. 4980
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-097-21,042-00-00

Lease Name: Dargel Trust

Well Number: 1

Spot Location (QQQQ): 100W - NE - NE -

660 Feet from North / South Section Line

760 Feet from East / West Section Line

Sec. 15 Twp. 29 S. R. 18 East West

County: Kiowa

Date Well Completed: _____

Plugging Commenced: 11-1-07

Plugging Completed: 11-2-07

KCC DISTRICT AGENT PER CP 213

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	521	
				5 1/2	4978	2470

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set bridge plug at 3460', bailed 2 sacks cement with bailer, dug cellar, unpacked casing head, set floor, pulled slips, had 26" stretch, ripped casing at 2610', worked pipe, ripped casing at 2470', came free, pulled casing up to 1135', pumped 15 gel, 50 sacks, pulled to 550', pumped 50 sacks, pulled to 40', circulated with 20 sacks to surface.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67526

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Vincent Oil Corporation
State of KANSAS County, SEDGWICK, ss.

NOV 08 2007

CONSERVATION DIVISION
WICHITA, KS

Richard A. Hiebsch (Employee of Operator or Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Richard A. Hiebsch

(Address) 155 N. Market, Suite 700, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this _____ day of _____, 20

Yolanda Eubanks My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PK