

15-065-20485-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Graham County, Sec. 35 Twp. 9 Rge. 24 (E) (W) (W)

Location as "NE/CNW%SW%" or footage from lines NE NW NW
Lease Owner Don E. Pratt Oil Operation
Lease Name Sughart Shughart Well No. 1
Office Address P.O. Drawer 370 Hays, Kansas 67601
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 30 1971
Application for plugging filed September 30 1971
Application for plugging approved September 30 1971
Plugging commenced September 30 1971
Plugging completed September 30 1971
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface pipe				8 5/8"	204'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug was set @ 1,200' with 100 cubic ft. cement
2nd plug was set @ 215' with 25 cubic ft. cement
3rd plug was set @ 40' with 10 cubic ft. cement

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1971
CONSERVATION DIVISION
Wichita, Kansas
10-06-1971

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dreiling Oil Inc.
Address Victoria, Kansas 67671

STATE OF Kansas, COUNTY OF Ellis, ss.

L. Leo F. Dreiling, Pres. of Drlg. Contr. (employee of owner) or (owner/lessee/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

Leo F. Dreiling, Rt. # 2 Victoria, Kansas 67671
(Address)

Subscribed and sworn to before me this 1st day of October, 1971

My commission expires September 19, 1974

Joseph A. Hess
Notary Public.



DREILING OIL, INC.

Victoria, Kansas 67671

15-065-20485-00-00

Don E. Pratt Oil Operations WELL LOG

P.O. Drawer 370

Company Hays, Kansas 67601

Sec. 35 Twp. 9 Rng. 24

Farm ~~Sughart~~ ^{Sughart} ^{KCC} ^{ZAY} No. 1

Location NE NW NW

Total Depth 4,090'

County Graham

Comm. 9-25-71

Comp. 9-30-71

Elevation: 2,496 K. B.

Contractor

2,493 D. F.

2,495 G. R.

Casing Record
204' 8 5/8"

Cement Record
160 sacks of cement

Production:
D & A

Figures Indicate Bottom of Formations

0'	140'	Top Soil, Sand & Gravel
140'	170'	Blue Shale
170'	204'	Blue shale
204'	225'	Shale
225'	1362'	Shale & Sand
1362'	1696'	Shale
1696'	1895'	Sand
1895'	2142'	Red Bed & Shale
2142'	2168'	Anhydrite
2168'	2179'	Anhydrite
2179'	2543'	Anhydrite
2543'	2823'	Shale
2823'	3035'	Shale & Lime
3035'	3257'	Lime & Shale
3257'	3380'	Lime & Shale
3380'	3610'	Shale & Lime
3610'	3756'	Lime
3756'	3870'	Lime
3870'	3940'	Lime
3940'	4040'	Lime
4040'	4090'	Lime
4090'	T.D.	

RECEIVED
STATE CORPORATION COMMISSION
OCT 6 1971
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
County of Ellis)

I, Leo F. Dreiling, of Dreiling Oil, Inc., upon oath state that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Sughart #1.

Leo F. Dreiling
Leo F. Dreiling

Subscribed and sworn to before me this 1st day of October, 1971.

Joseph A. Jess
Joseph A. Jess, Notary Public



My Commission expires: September 19, 1974.