

20572
15-065-20572-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Section Plat grid for well location

Locate well correctly on above Section Plat

Graham County, Sec. 35 Twp. 9 Rge. 2 (E) W (W)
Location as "NE/CNW&SW" or footage from lines NE SW SW
Lease Owner Don E. Pratt Oil Operations
Lease Name Elmer Gano Well No. B-#2
Office Address P. O. Drawer 370, Hays, Kansas 67601
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-15 1972
Application for plugging filed 11-15 1972
Application for plugging approved 11-15 1972
Plugging commenced 11-15 1972
Plugging completed 11-15 1972
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4.050 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: Surface Pipe, 8 5/8", 212'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug was set @ 1,175' w/70 cu. ft. cement
2nd plug was set @ 215' w/20 cu. ft. cement
3rd plug was set @ 40' w/10 cu. ft. cement




(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor DREILING OIL, INC.
Address Rt. #2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Joe Hess, Sec. Treas. of Drlg. Contrc. of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe Hess
JOE HESS, Rt. #2, Victoria, Kansas 67671 (Address)



Subscribed and Sworn to before me this 21 day of November, 1972
Cecilia Basgall
CECILIA BASGALL Notary Public.

DREILING OIL, INC.

Victoria, Kansas 67671

15-065-20572-00-00

Don E. Pratt Oil Operation

WELL LOG

P.O. Drawer 370

Company Hays, Kansas 67601

Sec. 35 Twp. 9 Rng. 24

Farm Elmer Gano No. B-#2

Location NE SW SW

Total Depth 4,050'

County Graham

Comm. 11-8-72 Comp. 11-15-72

Elevation: 2501 K. B.

Contractor Dreiling Oil, Inc.
Rt. #2
Victoria, Kansas 67671

2498 D. F.

2496 G. R.

Casing Record

Cement Record

Production:

212' - 8 5/8"

165 sacks cement

D & A

Figures Indicate Bottom of Formations

0'	215'	Sand & Shale
215'	470'	Shale
470'	1380'	Shale
1380'	1940'	Shale & Sand
1940'	2138'	Shale-Red Bed
2138'	2173'	Anhydrite
2173'	2380'	Shale
2380'	2970'	Shale
2970'	3500'	Shale & Lime
3500'	3685'	Lime
3685'	3780'	Lime & shale
3780'	3860'	Lime
3860'	4050'	Lime
4050'	T.D.	

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1972
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Joe Hess, Secretary Treasurer, of Dreiling Oil, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Elmer Gano B-#2.

Joe Hess
JOE HESS

Subscribed and sworn to before me this 21st day of November, 1972



Cecilia Basgall
CECILIA BASGALL NOTARY PUBLIC

My Commission Expires: September 13, 1976.