

15-065-03500-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH

Graham County, Sec. 36 Twp. 9 Rge. 24 (E) (W) x

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner D. G. Hansen

Lease Name George Gano Well No. #2

Office Address Box 187, Logan, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 8-2-67 19

Application for plugging filed 7-28-67 19

Application for plugging approved 19


Plugging commenced 8-4-67 19

Plugging completed 8-9-67 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation Depth to top Bottom Total Depth of Well 4040' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 5 1/2" | 4039' | 3040.14' |
| | | | | 8 5/8" | 207' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3850', set 15' rock bridge. Mixed and ran 5 sacks cement thru dump bailer. Squeezed hole with 5 sacks gel and 2 sacks hulls. Gel from 1560' to 1260'. Followed with 100 sacks cement. Cement from 1260' to 950'. Followed with 16 sacks gel and 3 sacks hulls. Gel from 950' to 210'. Followed with 20 sacks cement. Cement from 210' to 150'. Followed with 3 sacks gel. Gel from 150' to 30'. Displaced with 5 sacks cement. Cement from 30' to base of cellar.

Rec'd 8-14-1967

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.

Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) W. C. Spencer Sec.

Box 364, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 10 day of August, 19 67

My commission expires October 1968

Sidney D. Miller Notary Public.



15-065-03500-00-02

WELL LOG

OPERATOR D. G. Hansen SEC. 36-9-24
 WELL NAME George Gano #2 LOC. SE SE SE
 TOTAL DEPTH 4040' COUNTY Graham
 COMM. July 24, 1961 COMP. August 2, 1961 STATE Kansas
 RIG NO. 1 ELEVATION 2469' K.B.
 CASING: Ran 207.18' (10 jts.) 8-5/8" OD Surface Casing. PRODUCTION: Producing
 Set 5-1/2" OD Casing @4039' (132 jts.)

All measurements taken from the top of rotary bushing.

| FROM | TO | FORMATION | DEVIATION FROM VERTICAL | REMARKS: |
|------|------|---------------|-------------------------|---------------|
| 0 | 830 | Shale & Sand | | |
| 830 | 1300 | Sand & Shale | | |
| 1300 | 1590 | Shale | | |
| 1590 | 1840 | Sand | | |
| 1840 | 2088 | Red Bed | | |
| 2088 | 2124 | Anhydrite | | |
| 2124 | 2455 | Shell & Shale | | |
| 2455 | 2665 | Shale & Lime | 00 - 2500 | |
| 2665 | 2935 | Lime & Shale | 00 - 2750 | |
| 2935 | 3115 | Shale & Lime | 00 - 3000 | |
| 3115 | 3315 | Lime & Shale | 00 - 3250 | |
| 3315 | 3505 | Shale & Lime | 00 - 3500 | |
| 3505 | 3710 | Lime & Shale | | |
| 3710 | 3795 | Shale & Lime | 00 - 3750 | |
| 3795 | 3886 | Lime & Shale | | DST 3874-3886 |
| 3886 | 3970 | Lime | | DST 3955-3970 |
| 3970 | 3990 | Lime & Shale | | DST 3967-3990 |
| 3990 | 4010 | Lime | 00 - 4000 | DST 3986-4010 |
| 4010 | 4040 | Lime & Shale | | |

RECEIVED

AUG 10 1961

D. G. HANSEN

Time.....

STATE OF KANSAS)
 COUNTY OF SEDGWICK) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-6 DRILLING CO.

By G. F. Galloway

G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 8th day of August, 1961.

Notary Public
S. 20 1953

Vicky Jacobs
Vicky Jacobs - Notary Public