


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

GRAHAM County, Sec. 3 Twp. 9S Rge. 25 (XXXXXX) (W)

Location as "NE/CNW%SW%" or footage from lines C NE SW
Lease Owner EMPIRE DRILLING COMPANY
Lease Name KNOBEL Well No. 1
Office Address 650 FOURTH NATIONAL BANK BLDG., WICHITA 2, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 15 19 62
Application for plugging filed August 15 19 62
Application for plugging approved August 15 19 62
Plugging commenced August 15 19 62
Plugging completed August 15 19 62
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface	Sand & Shale	0	160	8 5/8	158	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 540' with 20 sacks cement.
Plug set at 160' with 20 sacks cement.
Plug set at 35' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1962
CONSERVATION DIVISION
Wichita, Kansas
8-28-62


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY
Address 650 FOURTH NATIONAL BANK BLDG., WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
DAN J. KORNFELD (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
650 Fourth National Bank Bldg, Wichita 2, Ks.
(Address)

Subscribed and sworn to before me this 23th day of August, 19 62



Lucille H. Harr
Notary Public.

LOG

COMPANY: EMPIRE DRILLING COMPANY
 CONTRACTOR: EMPIRE DRILLING COMPANY
 FARM: KNOBEL #1
 LOCATION: C NE SW Section 3-9S-25W, Graham County, Kansas
 COMMENCED: August 7, 1962 ELEVATION: 2531 KB
 COMPLETED: August 15, 1962 POTENTIAL: D & A

0	to	160	Surface - Sand & Shale
160	to	1550	Shale & Shells
1550	to	2050	Shale & Sand
2050	to	2223	Shale & Shells
2223	to	2260	Anhydrite
2260	to	2839	Shale & Shells
2839	to	3530	Shale & Lime
3530	to	3555	Lime
3555	to	3810	Lime & Shale
3810	to	3860	Lime
3860	to	3895	Lime & Shale
3895	to	4020	Lime
4020	to	4070	Lime & Shale
4070			Rotary Total Depth

SET: 158 of 8 5/8" with 100 sacks

WELEX ELECTRIC LOG TOPS:	Hegbner	3790	-1259
	 	3812	-1281
	No Lansing		
	Zone 2	3857	-1326
	Zone 2A	3870	-1339
	Zone 6	3965	-1434
	Zone 6 A	3988	-1457
	Zone 7	4008	-1477
	Zone 8	4028	-1497
	Base Kansas City	4058	-1527
	Welex Total Depth	4069	

RECEIVED
 STATE CORPORATE COMMISSION
 AUG 28 1962
 CONSERVATION DIVISION
 Wichita, Kansas
 8-28-62

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Knobel #1, C NE SW Section 3-9S-25W, Graham County Kansas, as reflected by the files of Empire Drilling Company.

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 23th day of August, 1962.

Lucille H. Harr
 Lucille H. Harr, Notary Public

