

15-065-21331-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County. Sec. 3 Twp. 9 Rge. 25 EW  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C-SE-NW

Lease Owner John Roy Evans

Lease Name Keith Well No. #1

Office Address Box 385 Claflin, Ks 67525

Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed 1-7 1981

Application for plugging filed 1-7 1981

Application for plugging approved 1-7 1981

Plugging commenced 1-7 1981

Plugging completed 1-7 1981

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 1-7 1981

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Baltazor

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4030'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	275'	8 5/8	260'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st Plug set at 1150' with 70 sacks of cement 50-50 poz 6% gel

2nd Plug set at 250' with 20 sacks of cement 50-50 poz 6% gel

3rd Plug set at 40' with 10 sacks of cement 50-50 poz 6% gel

5 sacks cement in rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing

STATE OF Kansas COUNTY OF Graham, ss.  
Jerry M. Helberg (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Jerry M. Helberg

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 12 day of January, 1981

Wayne E. Minium  
Notary Public.

My commission expires \_\_\_\_\_



1-13-81

DRILLERS LOG

KEITH #1

CASING RECORD:

8 5/8" set at 260'

TOTAL DEPTH:

4030'

DESCRIPTION:

C-SE-NW  
Sec. 3-9-25 Graham County, Ks.

OPERATOR: John Roy Evans

CONTRACTOR: Helberg Oil Co.

COMMENCED: December 17, 1980

COMPLETED: January 7, 1981

FORMATION	FROM	TO	RESULTS
Shale	0	180	
Shale	180	282	
Shale	282	785	
Shale & Sand	785	1453	
Shale	1453	1860	
Shale & Sand	1860	2008	
Shale & Sand	2008	2177	
Shale & Sand	2177	2199	
Anhydrite	2199	2233	
Shale & Sand	2233	2270	
Shale	2270	2446	
Shale & Lime	2446	2558	
Shale & Lime	2558	2700	
Shale	2700	2816	
Shale & Lime	2816	2939	
Shale	2939	3070	
Shale	3070	3153	
Shale & Lime	3153	3225	
Shale & Lime	3225	3320	
Shale & Lime	3320	3395	
Shale & Lime	3395	3423	
Shale & Lime	3423	3477	
Shale & Lime	3477	3547	
Shale & Lime	3547	3630	
Shale & Lime	3630	3699	
Shale & Lime	3699	3769	
Shale & Lime	3769	3834	
Lime	3834	3846	
Shale & Lime	3846	3891	
Lime	3891	3941	
Lime	3941	3990	
Lime	3990	4030	
T.D.	4030		D&A

I certify that the above is a true and correct copy of the log to the best of my knowledge.

HELBERG OIL COMPANY

*Jerry M. Helberg*  
Jerry M. Helberg

Subscribed and sworn to before me this 12 day of January 1981.

*Wayne E. Minium*  
Notary Public

My commission expires

