


15-065-20618-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 4 Twp. 9 Rge. 25 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines. NW SW NW
Lease Owner Palomino Petroleum
Lease Name Knoll Well No. F #1
Office Address 304 Insurance Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-17 1973
Application for plugging filed 7-17 1973
Application for plugging approved 7-17 1973
Plugging commenced 7-17 1973
Plugging completed 7-17 1973
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	210'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug was set @ 1,325' w/110 cu. ft. cement
2nd plug was set @ 215' w/30 cu. ft. cement
3rd plug was set @ 40' w/ 10 cu. ft. cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1973
CONSERVATION DIVISION
Wichita, Kansas
7-23-73


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dreiling Oil, Inc.
Address Rt. #2, Victoria, Kansas 67671

STATE OF KANSAS COUNTY OF ELLIS, ss.
I, Joe Hess, Sec. Treas. of Drlg. Contrc. (employee of owner, or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
JOE HESS, Rt. #2, Victoria, Kansas 67671
(Address)

Subscribed and Sworn to before me this 20th day of July, 1973



September 13, 1976

Cecilia Basgall
Notary Public.

DREILING OIL, INC.

Victoria, Kansas 67671

WELL LOG

Company	Palomino Petroleum 304 Insurance Building Wichita, Kansas 67202		Sec. 4	Twp. 9	Rng. 25
Farm	Knoll No. F - #1		Location	NW SW NW	
Total Depth	4,070'		County	Graham	
Comm.	7-9-73 Comp. 7-17-73		Elevation:	2554	K. B.
Contractor	Dreiling Oil, Inc. Rt. #2 Victoria, Kansas 67671			2551	D. F.
				2549	G. R.

Casing Record	Cement Record	Production:
210' - 8 5/8"	150 sacks cement	

Figures Indicate Bottom of Formations

0'	155'	Sand, Top Soil
155'	210'	Shale
210'	273'	Shale
273'	1370'	Shale & Sand
1370'	1660'	Shale & Hard Sand
1660'	1830'	Hard Sand & Shale
1830'	2010'	Sand
2010'	2119'	Shale
2119'	2240'	Shale & Red Bed
2240'	2280'	Anhydrite
2280'	2340'	Shale
2340'	2985'	Shale
2985'	3258'	Shale & Lime
3258'	3420'	Lime
3420'	3675'	Lime & Shale
3675'	4070'	Lime
4070'	T.D.	

State of Kansas)
)ss
County of Ellis)

I, Joe Hess, Secretary Treasurer, of Dreiling Oil, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Knoll F #1.

Joe Hess

JOE HESS

Subscribed and sworn to before me this 20th day of July, 1973.



Cecilia Basgall

Cecilia Basgall Notary Public

My commission expires: September 13, 1976.

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1973
CONSERVATION DIVISION
Wichita, Kansas
7-23-73