


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-065-03121-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Graham County, Sec. 6 Twp. 9S Rge. 25 (W)  
Location as "NE/CNW&SW" or footage from lines NE NE NE Oil  
Lease Owner Imperial Oil of Kansas, Inc.  
Lease Name Victory Life Ins. Co. Well No. 1  
Office Address 780 Fourth National Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed January 1, 1959 19  
Application for plugging filed June 12, 1961 19  
Application for plugging approved June 12, 1961 19  
Plugging commenced June 18, 1961 19  
Plugging completed June 21, 1961 19  
Reason for abandonment of well or producing formation  
Commercial quantities of oil depleted.  
If a producing well is abandoned, date of last production May, 1961 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius  
Producing formation Lansing-KC Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4080 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	228'	Not pulled
				5-1/2"	4080'	2496'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

First plug set at 225' with 25 sacks of cement; next plug set at 40' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 2 1961

CONSERVATION DIVISION  
Wichita, Kansas


10-2-61

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Great Bend, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
William A. Sladek (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) William A. Sladek Prod. Geol.  
780 Fourth Nat'l Bldg., Wichita, Ks.  
(Address)

Subscribed and Sworn to before me this 29th day of September, 19 61  
Elaine Wilkening  
Elaine Wilkening Notary Public.



15-065-03121-00-00

**RECEIVED**  
STATE CORPORATION COMMISSION

DRILLER'S LOG

JUN 8 1961 6-8-61

Imperial Oil of Kansas, Inc.  
780 Fourth National Building  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Victory Life Ins. Co. No. 1  
NE NE NE Sec. 6-9S-25W  
Graham Coutny, Kansas

Total Depth: 4080'

Commenced: 12-18-58 Completed: 1-1-59

Contractor: Imperial Oil of Kansas, Inc.  
Wichita 2, Kansas

Elevation: 2572' R.B.  
Production: State Potential:  
P 312 BOPD - NW  
Gravity - 36°

Casing Record: Set 8-5/8" Surface Pipe at 228' with 150 sacks cement.  
Set 5-1/2" Production Pipe at 4080' with 125 sacks cement.

Figures indicate bottom of formations:

Surface Sand & Shale	228'
Shale & Shells	1210'
Shale, Shells & Sand	1750'
Shale & Shells	2278'
Anhydrite	2316'
Shale & Shells	2735'
Shale & Lime	3860'
Lime	4080'
Total Depth	4080'

TOPS

Anhydrite	2278'	(-294)
Heebner	3819'	(-1247)
Toronto	3840'	(-1268)
Lansing	3858'	(-1286)
Rotary Total Depth	4080'	(-1508)

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: A L Bacon  
Vice-President

Subscribed and sworn to before me this 2nd day of June, 1959.

My Commission Expires:

July 7, 1962

Mona L. Latier  
Mona L. Latier-Notary Public

