


STATE CORPORATION COMMISSION

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

13-065-00014-00-00
WELL PLUGGING RECORD

Graham County, Sec. 8 Twp. 9-S Rge. 25 (E) (W) X

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNWxSWx" or footage from lines SW NW SW
 Lease Owner Empire Drilling Company
 Lease Name Williams Well No. 1
 Office Address 650 Fourth National Bank Building, Wichita 2, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed January 16, 1962 19
 Application for plugging filed January 16, 1962 19
 Application for plugging approved January 16, 1962 19
 Plugging commenced January 16, 1962 19
 Plugging completed January 16, 1962 19
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4130 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Shale	0	200'	8 5/8"	168'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 540' with 20 sacks cement.
 Plug set at 165' with 20 sacks cement.
 Plug set at 40' with 10 sacks cement.


RECEIVED
 STATE CORPORATION COMMISSION
 JAN 26 1962
 CONSERVATION DIVISION
 Wichita, Kansas
 1-26-62

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Empire Drilling Company
 Address 650 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss. Irwin Kornfeld (employee of owner) or XXXXXX of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Irwin Kornfeld
650-4th Nat'l. Bank Bldg., Wichita 2, Kansas
 (Address)

SUBSCRIBED AND SWORN to before me this 25th day of January, 19 62
Lucille H. Harr
 Lucille H. Harr Notary Public.



15-065-00014-00-00

LOG

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1962

CONSERVATION DIVISION
Wichita, Kansas

1-26-62

COMPANY: Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: Williams # 1
 LOCATION: SW NW SW of Section 8-9s-25w, Graham County, Kansas
 COMMENCED: January 5, 1962. ELEVATION: 2599 KB
 COMPLETED: January 16, 1962. POTENTIAL: D & A

0	to	200	Surface Shale
200	to	1490	Shale
1490	to	2291	Shale-Shells
2291	to	2328	Anhydrite
2328	to	2585	Shale-Shells
2585	to	3170	Shale-Lime
3170	to	3225	Lime
3225	to	3337	Lime-Shale
3337	to	3470	Lime
3470	to	3900	Lime-Shale
3900	to	3940	Lime-Chert
3940	to	3970	Lime
3970	to	4025	Lime-Shale
4025	to	4067	Lime-Chert
4067	to	4110	Lime
4110	to	4130	Lime-Chert-Shale
4130			Rotary Total Depth

SET: 168' of 8 5/8" casing with 100 sacks cement.

ELECTRIC LOG TOPS:

Heebner	3858	-1259
Toronto	3886	-1281
Lansing	3899	-1300
Base Kansas City	4128	-1529
Schlumberger TD	4140	

CERTIFICATION

I, Irwin Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Williams # 1, SW NW SW of Section 8-9S-25W, Graham County, Kansas, as reflected by the files of Empire Drilling Company.

Irwin Kornfeld

Irwin Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 25th day of January, 1962.

Lucille H. Harr

Lucille H. Harr, Notary Public



My commission expires Oct. 21, 1962.