

State of Kansas



15-065-20060-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1967
7-18-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clarence Michaels of Sage Drlg Co., Inc., has this
date requested permission to plug the following described well:

Mr. Michaels guarantees payment of the plugging fee.

Operator's full Name: H. C. Bennett,

Complete Address: 1212 Union Nat'l Bank Bldg., Wichita, Kansas.

Lease Name: McElroy Well No. 1

Location: CS/2-NE-SE Sec. 34 Twp. 9 Rge. (E)(W) 22

County Graham Total Depth 3845 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Michaels was instructed to plug the well as follows:

241'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1365 to 1562'.

Set plug from 1590' to 1290' with 80 Sx. cement.

Set plug from 240' to 180' with 20 Sx. cement.

Set plug @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent