



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-2065-20527-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1972
CONSERVATION DIVISION
Wichita, Kansas
02-17-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated, has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Elmer Dreiling Well No. A-1

Location: 1320' EWL & 440' SNL of NW/Sec. 32 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4092' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Draper was instructed to plug the well as follows:

238'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1275' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent