



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-20236-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerb Ogle of Red Tiger Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated.

Complete Address: 1515 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Kurtz Well No. 1

Location: NW-NW-NW Sec. 34 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4116' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

225'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to to 1165' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED

STATE CORPORATION COMMISSION

JUL 1 1969 Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas

M. L. Dribala
Conservation Division Agent