



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 11 1972

CONSERVATION DIVISION  
Wichita, Kansas

04-11-1972

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

15-065-20539-00-00

Mr. Bill Owens of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Owens guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name: Kurtz Well No. 1-B

Location: NW-SE-NW Sec. 34 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4095' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Owens was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 825'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 110 Cu. Ft. cement thru DP. Pull DP to 210' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent