



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-065-01055-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JUL 18 1963  
07-18-1963  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Bob White of Empire Drilling Co. has this

date requested permission to plug the following described well:  
Time Petr. Associates & Empire Drlg Co.

Mr. White guarantees payment of the plugging fee.

Operator's full Name: Time Petroleum Associates & Empire Drlg. Co.,

Complete Address: 650 4th National Bldg., Wichita, Kansas.

Lease Name: Shughart Well No. 1

Location: NE-SW-NE Sec. 35 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4080 Oil Well         

Gas Well          Input Well          SWD Well          D & A X          Lost Hole         

Mr. White was instructed to plug the well as follows:

162'--8 5/8" Surface Pipe, cement circulated.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx cement.

|   |   |  |
|---|---|--|
| " | " | 160' with 1/4 sk hulls & 20 Sx cement. |
| " | " | 35' with 1/2 sk hulls & 10 Sx cement.  |

Very truly yours,

M. L. Nichols  
 Conservation Division Agent