



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-065-20304-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company, has this
date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: Geo. Reed and C & G Drilling Company,

Complete Address: 1301 Union National Building, Wichita, Kansas.

Lease Name: Elmer ~~Cano~~ ^{KCC} ZAP Well No. 117

Location: NW-NW-SW Sec. 35 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4060 ~~1011~~ Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

201'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1970
02-06-1970
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

A. L. Nichols
Conservation Division Agent