



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-065-20485-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 4 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
10-4-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Shughart Well No. 1

Location: NE-NW-NW Sec. 35 Twp. 9 Rge. (E)(W) 24

County: Graham Total Depth 4090' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

204'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 975'.

Circulate hole with heavy mud, pull DP to 1200' and displace 100 Sx.  
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent