

KANSAS

*Y* STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 17 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
11-17-1972

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-20572-00-00

Operator's Full Name Don Pratt,

Complete Address Box #370, Hays, Kansas.

Lease Name Elmer Gano Well No. B-2

Location NE-SW-SW Sec. 35 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4050'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.       

Operation Completed: Hour 3:30 PM Day 15 Month 11 Year 1972

The above well was plugged as follows:

212'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 110 Cu. Ft. cement  
thru DP from 1175' to 850'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *R. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 11/17/72  
INV. NO. 6644-W