

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20207-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1969
CONSERVATION DIVISION
Wichita, Kansas

2-24-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name Schweitzer Well No. 1

Location CE/2-SE-NE Sec. 16 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3935'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 2:30 PM Day 19 Month 2 Year 1969

The Above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 155 Sx.
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 100 Sx. cement thru
DP from 1075' to 750'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215'
to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
wellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 2/25/69
INV. NO. 9377-W