

KANSAS

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20364-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1971
CONSERVATION DIVISION
Wichita, Kansas
9-20-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address Box #370, Russell, Kansas.

Lease Name Harvey Well No. 1

Location SE-SW-NW Sec. 19 Twp. 9 Rge. (E) (W) 23

County Graham ORIGINAL TD 3995'
Total Depth 3955'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling, Incorporated,

Address Box #221, Great Bend, Kansas License No. 637

Operation Completed: Hour 11:00 AM Day 17 Month 9 Year 1971

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.
3994'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3935'. Top perforations from 3921' to 3926'.

Sanded well back to 3900' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 11 sacks gel then 105 Sx. cement from 1190' to 850', followed with 16 sacks gel from 850' to 210' then 20 Sx. cement from 210' to 150', followed with 3 sacks gel from 150' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--300#. Final shut-in pressure--100#. (Recovered 1600' 5 1/2" casing). (Mudding and cementing by Allied Cmtg.).

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 9-22-71

INV. NO. 4348-W