

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED

STATE CORPORATION COMMISSION

OCT 28 1970

CONSERVATION DIVISION
Wichita, Kansas

10-28-70

15-065-20387-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Harvey Well No. 2

Location NW-SW-NW Sec. 19 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3976'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 8:45 AM Day 26 Month 10 Year 1970

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'/. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hullsand 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. G. Nichols
Well Plugging Supervisor

DATE 10/28/70

INV. NO. 2766-W