

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-065-21,677-<sup>✓</sup>00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name RAINS AND WILLIAMSON OIL CO. INC.

Complete Address 435 PAGE COURT-220<sup>W</sup> DOUGLAS, WICHITA, MO. 67202

Lease Name GANO Well No. #3

Location NW-SE-NE Sec. 30 Twp. 9<sup>S</sup> Rge. 23<sup>W</sup> (East)(West)

County GRAHAM Total Depth 4080<sup>FT</sup>

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor RAINS AND WILLIAMSON DRILLING (RICH PEAK)

Address 435 PAGE COURT  
220 WEST DOUGLAS, WICHITA, MO. 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 1:15<sup>PM</sup> Day: 12<sup>th</sup> Month: AUG. Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 282<sup>FT</sup> SP. CUC. w/ 200<sup>ST</sup> COMMON - 2% GEL - 3% CA-CL. [SUN] <sup>B34</sup>  
ORDERED 140<sup>ST</sup> 50/50 FORMIX 4% GEL - 3% CA-CL. & 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>ST</sup> Plug @ 1200 FT. w/ 80<sup>ST</sup> CMT.

2<sup>ND</sup> Plug @ 300 FT. w/ 40<sup>ST</sup> CMT.

3<sup>RD</sup> Plug - SOLID BRIDGE @ 4/8<sup>FT</sup> 1/0 w/ 10<sup>ST</sup> CMT.

10<sup>ST</sup> IN RAT HOLE (CIRCULATE)

CEMENTED BY SUN CMT.

Amount of Surface Casing: 282<sup>FT.</sup>

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED

STATE CORPORATION COMMISSION

AUG 23 1982

CONSERVATION DIVISION  
Wichita, Kansas

Signed: \_\_\_\_\_

Conservation Division Agent

8-23-82

INVOICED

DATE 9-8-82

INV. NO. 1046-W