

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1974
08-12-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20692-00-00

Operator's Full Name John O. Farmer, Inc.
Complete Address Box 352, 370 N. Wichita, ^{Russell} Wichita, Kansas
Lease Name Riggs "B" Well No. 1
Location NE NE NE Sec. 1 Twp. 9 Rge. (E) (W) 24
County Graham Total Depth 3836'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 9:30 P Day 6 Month 8 Year 1974

The above well was plugged as follows:

RTD 3836' 8 5/8 csg set at 201' cwc 150 sk. .Cmt Mat 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, displaced 70 sk cmt at 1300' thru drill pipe.

Heavy mud to 200' & displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set

cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 8/13/74

INV. NO. 9694-W