

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-065-02153-00-00

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW-NW-SW

SEC. 2 TWP. 9 RGE. 24W

Dry Hole *** Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Wagner

Operator Honaker - Davis Drilling Co. Address 2008 Lakin. Great Bend, Kansas.

Field _____ County Graham

Total Depth 4010' Feet.

(Describe briefly the manner in which the well was plugged)

Plugging Contractor. - Honaker - Davis Drilling Co.

Plugging Contractor's License No. - _____

Address. - 2008 Lakin. Great Bend, Kansas.

Surface pipe - 8 5/8" set @ 209' c.w.c. 175 sx.

Filled hole with heavy mud to 200' from top, 1/2 sx. hulls, H.O.W.C.O.

plug and 15 sx. cem. through drill pipe. Mud to 40' from top, 1/2 sx.

hulls, H.O.W.C.O. plug and 10 sx. cem. to base of cellar.

PLUGGING
FILE SEC. 2 T. 9 R. 24W
BOOK PAGE 97 LINE 39

RECEIVED
CORPORATION COMMISSION
SEP 8 1956
09-08-1956
CONSERVATION DIVISION
Wichita, Kansas

Milton Eberhart
District Conservation Agent
Date 9-6-56

Langreen