

*AL* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

AUG 8 1972  
*08-08-1972*  
CONSERVATION DIVISION  
Wichita, Kansas

*15-065-20557-00-00*

Operator's Full Name Clinton Oil Company,

Complete Address 217 North Water, Wichita, Kansas.

Lease Name Orval Keith Well No. 1-V

Location SE-SW-NW Sec. 2 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4000'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Garvey Drilling Company,

Address Box #1164, Great Bend, Kansas. License No.       

Operation Completed: Hour 1:45 PM Day 6 Month 8 Year 1972

The above well was plugged as follows:

214'--10 3/4" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1150' and displaced 140 Cu. Ft. cement  
thru DP from 1150' to 825'. Pulled DP to 245' and displaced 45 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 15 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *R. L. DeChalk*  
Well Plugging Supervisor

INVOICED

DATE 8/8/72  
INV. NO. 6133-W