

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 29 1973  
01-29-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-065-20580-00-00

Operator's Full Name Clinton Oil Company,

Complete Address 217 North Water, Wichita, Kansas.

Lease Name Wilma M. Harvey Well No. 1-V

Location SW-NE-SE Sec. 2 Twp. 9 Rge. (E) (W) 24

County Graham Total Depth 4040'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kansas. License No.       

Operation Completed: Hour 8:00 PM Day 24 Month 1 Year 1973

The above well was plugged as follows:

220'--10 3/4" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 165 Cu. Ft. cement  
thru DP from 1225' to 865'. Pulled DP to 245' and displaced 40 Cu. Ft. cement thru  
DP from 245' to 175'. Pulled DP, set bridge @ 40' with 1 sack hulls and 20 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. D. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 1/30/73

INV. NO. 6902-W