

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1961
08-16-1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-065-00445-00-00

File No. _____ County: Graham
Location: SW SW SW Sec. 3 Twp. 9 Rge. _____ (E) _____ (W) 24
Name of Field: _____ Total Depth: 3965

I have this date completed supervision of plugging of:

Lease Name: Keith Well No. 1

Operator's Full Name: Empire Drg Co

Complete Address: 650 4th Natl Bk Bldg Wichita, Kansas

Plugging Contractor: Knight Casing Pumping Co

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 10 Month 8 Year 61

The above well was plugged as follows:

8 5/8" 224' circulated with cement - 5 1/2" 3968' with 75 sax cement- PB
3943' - perforated 3824'.

Filled with sand to 3800', set 4 sax cement with dump bailer, pulled
1300' 5 1/2" to 550', circulated hole with heavy mud - pit mud from new
well - displaced 20 sax cement through 5 1/2" at 550', heavy mud tl 180',
displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', set
bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Knight Company pump truck.

Signed: Jewel M. Ogden
Conservation Division Agent

Reviewed: Harold J. Steen
Field Supervisor

Remarks:

INVOICED
DATE 8/14/61
INV. NO. 3623-W