

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-065-01585-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW SE SW

SEC. 3 TWP. 9 RGE. 24

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 4 Lease Keith 400 Brown Bldg.

Operator Empire Drg Co Address Wichita, Kans

Field _____ County Graham

Total Depth 3920 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 177' circulated with cement - 5 1/2" at 3902' with 100
sax cement behind.

Sand to 3890', set 6 sax cement with dump bailer - pulled

1703' 5 1/2" - pumped hole full mud (38 sax Gel), set cementing plug at
200' with 20 sax cement, heavy mud to 35', set rock and 10 sax cement
to bottom cellar.

Leson Lett
District Conservation Agent

Date 8-7-57

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1957
08-13-1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 3 T 9 R 24W
BOOK PAGE 36 LINE 44