

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

15-065-01601-00-00

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW SE SE

SEC. 3 TWP. 9 RGE. 24

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 6 Lease Keith

Operator Empire Dng Co Address 400 Brown Bldg Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3930 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 171' circulated with cement - 5 1/2" 3930' with 75 sax  
cement behind - perforated ~~38~~ 3914'.

Filled with sand to 3900', set 4 sax cement with dump bailer,  
pulled 1410' 5 1/2" - mudded hole through 5 1/2" with heavy rotary mud,  
set cementing plug at 200', rock and 20 sax cement, heavy mud to  
35', set rock and 10 sax cement to bottom cellar.

*E. J. ...*

District Conservation Agent

Date 8-24-57

PLUGGING  
FILE SEC 3 T 9 R 24  
BOOK PAGE 30 LINE 24

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 25 1957  
08-29-1957