

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-065-01602-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NE SW SE

SEC. 3 TWP. 9 RGE. 24

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 7 Lease Keith

Operator Empire Drg Co Address 400 Brown Bldg Wichita, Kans

Field _____ County Graham

Total Depth 3940 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 170' circulated with cement - 5 1/2" 3940 with 75 sax
cement behind - perforated 3889'.

Filled with sand to 3875', set 5 sax cement with dump bailer,

pulled 1660' 5 1/2" - mudded hole with heavy rotary mud through 5 1/2" -

set bridge at 200', rock and 20 sax cement, heavy mud to 35', set

rock and 10 sax cement to bottom cellar.

Edon Petty

District Conservation Agent

Date 8-22-57

PLUGGING
FILE SEC 3 T 9 R 24W
BOOK PAGE 40 LINE 42

RECEIVED
STATE CORPORATION COMMISSION
08-29-1957
AUG 29 1957
CONSERVATION DIVISION
Wichita, Kansas