

15-065-00195-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Graham

County, Sec. 84 Twp 9 Rge. 22 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines Center NW NW NW

Lease Owner Yockey Oil Co.

Lease Name Walker Funsoll #1 Well No.

Office Address Hillside Bldg. Wakenoy, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed April 1, 1951 19

Application for plugging filed 19

Application for plugging approved April 5, 1951, J.P. Roberts letter 19

Plugging commenced April 1, 1951 19

Plugging completed April 1, 1951 19

Reason for abandonment of well or producing formation dry


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes; by telephone

Name of Conservation Agent who supervised plugging of this well Eidan Potty

Producing formation none Depth to top Bottom Total Depth of Well 4023 Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Anhydrite		1650		8 5/8	100	cemented in
Topeka		3351				
Hochbener		3575				
Lansing Kansas City		3610	3734			
Arbuckle		3990	4023			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top 170 feet to top feet for each plug set.

PLUG at 170 FT 1/2 sack mud 20 sack mixed cement
PLUG at 40 FT 1/2 sack mud 10 sacks mixed cement to top

APR 14 1951
CONSERVATION DIVISION
WICHITA, KANSAS

4-14-51

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Hillside Bldg. Wakenoy, Kansas

STATE OF Kansas COUNTY OF YOCKEY
Harry T. Watson, Supervisor of Yockey Oil Co., ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harry T. Watson
Wakenoy, Kansas

April 9th 1951 (Address)

9th

day of

19

Subscribed and sworn to before me this Feb. 28, 1955

Ernest J. Demas
Notary Public.

My commission expires

23-5091-s 8-50-10M

PLUGGING
FILE SEC 34T 9-RYW
BOOK PAGE 71-1 USE 33

15-065-00195-00-00

R. B. Osborn, President

Telephone Office 333
Telephone Residence 64

YOCKEY OIL CO., INC.
Drilling Royalties and Leases
Hille Bldg.

WAKEENEY, KANSAS

Drillers' Log WALKER RUSSELL NO. 1

Location:	NW-NW-NW-Sec. 34-9S-22W Graham County, Kansas	Date Spudded:	3-12-51
Operator:	Yockey Oil Co., Inc.	Rotary Completion:	4-1-51
Contractor:	Yockey Oil Co., Inc.	Total Depth:	4023
Surface Casing:	168' of 8-5/8" cemented 125 sacks cement circulated	Elevation:	2363 DF 2365 KB 2358 Gr
Oil String:	None Run - Plugged and abandoned 1 April 1951		

TOPS (KB)

Anhydrite	1830
Topeka	3351
Heebner	3573
Lansing-Kansas City	3610
Arbuckle	3993
Rotary Total Depth	4023

LOG

(Figures indicate bottom of formation)


Sand shale	0 to 130	Lime shale	3472
Shale	522	Lime	3701
Shale	840	Lime shale	3760
Sand and shale	1184	Lime shale	3839
Shale	1195	Lime shale	3884
Sand	1435	Lime	3888
Shale and shells	1721	Lime, shale and cong.	3980
Anhydrite	1755	Lime, Dolo	4023
Shale shells	2485	Total Depth	4023
Shale and lime	3033		
Shale	3198		
Shale and lime	3288		
Lime	3351		

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1951
CONSERVATION DIVISION
Wichita, Kansas
4-14-51

The undersigned, Yockey Oil Co., Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Drilling Reports.

YOCKEY OIL CO., INC.

BY: R. B. Osborn Pres



Subscribed and sworn to before me this 9th day of April 1951

PLUGGING
FILE SEC 34-T-9-R2W
BOOK PAGE 74 LINE 33

Comm. Exp. 12-11-52