


15-065-00902-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Graham County. Sec. 26 Twp. 9 Rge. 24 (E) (W)
Location as "NE/CNW%SW%" or footage from lines NW NW SE
Lease Owner Honaker-Davis Drlg. Co.
Lease Name Drury Well No. 1
Office Address 2008 Lakin, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-16 19 56
Application for plugging filed 4-15 19 56
Application for plugging approved 4-15 19 56
Plugging commenced 4-16 - 3:00 A.M. 19 56
Plugging completed 4-16 - 5:30 A.M. 19 56
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4100 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	219	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 210'. Dumped in 1/2 sack hulls, Plug and 15 sacks cement through Drill pipe.
Filled hole with heavy rotary mud to 40'. Dumped in 1/2 sack hulls set plug and 10 sacks cement to bottom of cellar.

4/21/56
APR 21 1956

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Honaker-Davis Drlg. Co.
Address 2008 Lakin, Great Bend, Kansas


STATE OF KANSAS COUNTY OF BARTON, ss.
S. C. Lingreen (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. C. Lingreen
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of April, 19 56

My commission expires 6-25-59
Kenneth G. Fischer, Notary Public.

24-7368-S 3-53-20M



PLUGGING
FILE SEC 26 T 9 R
BOOK PAGE 55 LINE 4

DRILLERS LOG

Drury No. 1
Loc: NW NW SE
Sec: 26-9-24
Graham County, Kansas
Company: Monaker-Davis Drig. Co., et al
Contractor: Monaker-Davis Drig. Co.

Comm: 4-7-56
Comp: 4-18-56
Rotary Total Depth: 4100'
Casing: 8-5/8" at 218'
D & A

0	20	Top Soil & Clay	
20	90	Sand & Gravel	
90	155	Post Rock & Clay	8-5/8" casing cemented at
155	750	Blue Shale	219 with 175 sacks cement
750	950	Shale & Shells	and 3 sacks calcium chloride
950	1025	Sand	
1025	1225	Shale & Shells	
1225	1300	Sand	
1300	1750	Shale & Red Bed	
1750	1910	Sand	
1910	2145	Red Bed & Shale	
2145	2190	Anhydrite	
2190	2345	Shale & Shells	
2345	2400	Salt & Shale	
2400	4100	Line & Shale	D & A
4100		Rotary Total Depth	

I certify that this is the true and correct copy of the above log to the best of my knowledge.

H. S. Forles

H. S. Forles

Subscribed and sworn to before me this 20th day of April, 1956.

Kenneth G. Fischer
Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59



PLUGGING
FILE SEC 26 T 9 R 24 W
BOOK PAGE 55 LINE 4